

1. GENERAL

1.1 SCOPE

- .1 This section refers to the temporary facilities that will be required to accommodate construction.

1.2 STANDARDS

- .1 Within these Specifications reference is made to the following standards:
 - .1 CSA – Canadian Standards Association

1.3 PARKING

- .1 Parking space will be made available on Site. Maintain and administer this space as directed by the Engineer.

1.4 SECURITY

- .1 If deemed necessary by the Contractor, the Contractor shall provide and pay for responsible security personnel to guard the Site and the contents of the Site after working hours and during holidays.

1.5 FALSEWORK

- .1 Design and construct false-work in accordance with CSA S269.1-1975.

1.6 SCAFFOLDING

- .1 Design and construct scaffolding in accordance with CAN/CSA S296.2.

1.7 SANITARY FACILITIES

- .1 Provide sufficient sanitary facilities for workers in accordance with local health authorities.
- .2 Maintain such facilities in a clean condition.

1.8 MEASUREMENT AND PAYMENTS

- .1 There shall be no additional payment for any items specified in this section, unless otherwise identified by the Owner or the Engineer.

2. PRODUCTS (Not Applicable)

3. EXECUTION (Not Applicable)

END OF SECTION